FE-262WD

Diagram No. 1211-3

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

DESCRIPTIVE REPORT

Type of Survey ... Wire Drag & Side Scan Sonar

Field No. ... R/H-20-15-83/84

Office No. ... FE-262 WD

LOCALITY

New York

State ... Nong Island Sound

Locality ... The Race

19 83-84

CHIEF OF PARTY

LCDR D.D.Winter & LCDR R.K.Norris

LIBRARY & ARCHIVES

July 17, 1985

☆U.S. GOV. PRINTING OFFICE: 1980-766-230

YO SIGN OF SEE

12300 THO

HYDROGRAPHIC TITLE SHEET

FE-262 WD

INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.

FIELD NO.

R/H 20-15-83/84

State NEW YORK
General locality LONG ISLAND SOUND
Locality NORTHVILLE CORRIDOR - OFFSHORE LONGITUDE 072-08-00W to 072-01-00W.
Scale 1;20,000 Date of survey 26 Oct. 1983 - 26 Oct. 1984
Instructions dated June 17, 1983 & April 12, 1984 Project No. OPR-B660-RU/HE-83/84
Vesseß NOAA SHIPS RUDE (9040) and HECK (9140) (1984) (1983) Chief of party LCDR Robert K. Norris and LCDR Donald D. Winter
Surveyed by R.K. Norris, D.D. Winter, N.G. Millett, E.M. Clark, J.C. Talbott, T.G. Callahan Conargrams/ undings taken by echo sounder, hand lead, pole Klein S/Ns 088 & 223, DE719B S/Ns 5799,5497 & 621
Graphic record scaled by G.L.A., T.G.C., E.M.C. DSF 6000n S/Ns B051N,A116N
Graphic record checked by R.K.N., T.G.C., E.M.C., N.G.M., W.J.A.
Protracted by N/A Automated plot by N/A
Verification by Evaluation and Analysis Group, Hydrographic Surveys Branch, A.M.C.
Soundings in fathoms feet at MLW MLLW Predicted Tides Smooth Tides
REMARKS: All times are recorded in UTC. See Coast Pilot Report and Loran-C comparison data for OPR-B660-RU/HE-83/84, for additional data on this survey.
Awors and SURF V Rev 4/86

HYI PRO	DROGRAPHIC TITLE SHEET	i
ABODEFGHHJKLM.	PROJECT AUTHORITY CHARACTERISTICS AND LIMITS OF AREA SURVEYED SURVEY VESSELS HYDROGRAPHIC SHEETS EQUIPMENT AND TECHNIQUES CONTROL STATIONS CALIBRATION AND POSITION CONTROL DATES OF SURVEY REDUCTION AND PROCESSING OF DATA JUNCTIONS AND SPLITS COMPARISON WITH PRIOR SURVEYS COMPARISON WITH THE CHART ADEQUACY OF SURVEY INCOMPLETE ITEMS CURRENTS AND WINDS PERSONNEL	
Q. R.	GENERAL NOTES	
	PENDICES	
¥A.	ABSTRACT OF ELECTRONIC CORRECTORS-BASELINE CALIBRA-	
B. C. D.	ABSTRACT OF DAILY STATISTICS-ABSTRACT OF POSITIONS HORIZONTAL CONTROL	- A-42 - A-49 - A-50
E.	PNEUMO DEPTH GAUGE CALIBRATIONS	- A-53
₩G.	SHEET PARAMETERS	- A-55
H. ∗I.	SMOOTH TIDE REQUEST - FIELD TIDE NOTE	- A-59
₽K.	DANGERS TO NAVIGATION REPORT	- A-62
L. *M. *N.	SONAR COVERAGE ABSTRACT - TARGET ABSTRACT	- A-01

* = Data Removed from the Descriptive Report and filed with the field records.

DESCRIPTIVE REPORT TO ACCOMPANY
HYDROGRAPHIC SURVEY FE-262WP R/H 20-15-83/84
1:20,000 SCALE, 1983-1984
NOAA SHIPS RUDE & HECK
LCDR ROBERT K. NORRIS, COMDG. (1984)
LCDR Donald D. Winter, Comdg. (1983)

A. Project Authority

This project was conducted durins a two year period in accordance with Hydrographic Project Instructions OPR-B660-RU/HE-84 and OPR-B660-RU/HE-83; for the Southern New Ensland Coast. The 1984 instructions are dated April 12, 1984, with one amendment to these instructions, chanse No. 1 dated May 21, 1984. The 1984 instructions supersede the previous instructions issued for OPR-B660-RU/HE-83 dated 17 June, 1983; with two chanses to those instructions, dated 22 July and 8 December, 1983. The purpose of this project is to provide wire-dras and sonar clearance of the Northville Industries Corporation oil tanker route, to provide clearance depths over selected wreck sites, and to verify or disprove certain reported submersed wrecks along the south coast of New Ensland. - A charge *2 to the 1984 instructions were issued offer completion of this survey. This change does not affect this survey.

B. Characteristics and Limits of Area Surveyed

This report contains that area of the one mile wide tanker route from the junction with R/H 20-14-83/84 at lonsitude 072-08-00 W to the junction with R/H 20-16-84 at lonsitude 072-01-00 W. The 1983 survey work consisted of an initial sonar investigation with 100-percent coverage of the bottom in the corridor area utilizing 200 meter vessel track spacing and the sonar recorder operated at the 200 meter range scale. The amount of towfish cable set out over the stern was resularly adjusted in an attempt to operate the fish at 40 meters off the bottom, as indicated in section 7.12.1 of the Project Instructions. However, the bottom topography was very irregular in this area of Long Island Sound with depths ranging from nearly 300 feet in The Race to 30 feet in the vicinity of Valiant Rock and Race Rock. Therefore, this requirement could not always be met in all areas of this survey.-Concur

The 1984 survey work consisted of one sonar split line run in the vicinity of Race Rock and wire-dras clearance of several boulder fields located during 1983.

C. Survey Vessels

This survey was accomplished by the NOAA Ships Rude (9040) and Heck (9140).

D. Hydrosraphic Sheets

The hydrographic sheets used in this survey were made of mylar and were constructed with the Digital PDP 11/34 computer S/N AG22645 and Houston Instruments roll-bed plotter S/N 8731-8

aboard the Ship Rude.

The field sheets were plotted at a scale of 1:20,000 and were used aboard each vessel to hand plot the towins vessel's position while on line. A smooth sheet was also plotted aboard the ship usins the same equipment as described above. This smooth sheet was used to machine plot the towins vessel's position, to hand plot any tarsets or large contacts, to delineate the limits of rocky or boulder areas, and to illustrate the area covered by side scan sonar operations. The 1984 drag strip data was plotted at a scale of 1:20,000 as overlays to be used in conjunction with the smooth sheet. The field records are being sent to the Atlantic Marine Center for verification, and smooth plottins, and Evaluation and Aralysis.

E. Equipment and Techniques

All side scan sonar coverage was accomplished with the Klein systems provided by AMC. These systems consisted of a Model 521 recorder, a 100 KHz towfish, a K-Wins depressor and a towcable. Recorder Unit 223 was used aboard the HECK during the 1983 field season and recorder unit 88 was used aboard the RUDE, Sonar operations were completed during 1984 with recorder 88 used aboard the HECK.

To minimize the potential for damasins the towfish, the initial sonar investisation was first cautiously conducted at slack water in the vicinity of Valiant and Race Rocks where the irresular depths steeply rise from 300 feet to between 30 and 40 feet. The remainder of the survey was then investisated attemptins to operate the towfish at 40 meters off the bottom. In addition, a crossline was run at the constricted area of the corridor between Valiant and Race Rocks to insure that no large contacts exist in this area.

Del Norte rates obtained on fixes were recorded with Eaton Model 7000+ serial printers during this survey. These printers worked fairly well considering the fact that they were not designed to be operated in a marine environment. The printers would often type out a line of meaningless characters or rates from the previous fix before the current fix was recorded. The printer records were annotated such that these meaningless characters and extraneous rates were lined out leaving the correct fix rates clearly displayed.

A Raytheon model DE-719B echo sounder was operated and annotated concurrently durins all 1983 side scan sonar operations. A model DSF 6000N was operated durins all 1984 sonar and wire-dras operations. The echo sounder recordings were reviewed daily to ensure that no large objects located directly under the sonar towfish had sone undetected. During 1983, unit S/N 5799 was used aboard the Rude on JDs 299 and 300 through fix 119. This unit was removed from service on JD 300 as a result of poor analog recordings below 150 feet. Spare unit S/N 5497 was used aboard the Rude during the remainder of JD 300 and on JDs 307, 308, and 311. Unit S/N 6212 was used aboard the Heck on JD 300. During 1984 operations, unit BO51N was used aboard the RUDE and unit A116N was used aboard the HECK.

Although it is not anticipated that these sounding

records will be used for chartins purposes, the settlement and squat data for the Rude and Heck, obtained in Norfolk Harbor on 25 January 1983, is included in this report. No velocity corrections or settlement and squat determinations were actually conducted within or during this project. The 1984 wire-drag operations were conducted with standard ship wire-drag equipment and techniques. The soundings recorded were apparently not plotted by the field and no automated tapes of these soundings were submitted, therefore no plot of these soundings is available. The soundings F. Control Stations these soundings were scaled and smooth plotted during Evaluation and Analysis.

See the Evaluation Report, section 6.

Two electronic control stations were used for this survey. Station Ol was SAYBROOK LIGHTHOUSE (1861), at latitude 41-16-16.894 N and lonsitude 072-20-37.01% W with an elevation of 21.6 meters. Station O2 was NEW LONDON LEDGE LIGHTHOUSE (1932), located at latitude 41-18-20.79% N and lonsitude 072-04-40.51% W with an elevation of 17.7 meters. Both stations were located by NGS and the adjusted positions for these stations were obtained from published NGS horizontal control data. All stations are of Third-Order, Class I control accuracy or better. The station positions are based upon the North American Datum of 1927.

G. Calibration and Position Control

Vessel positioning for all work was accomplished with the Del Norte 520 series electronic positioning equipment operated at a frequency of 9400 MHz in the range-range mode. A listing of DMU and master units used by the vessels during this survey are listed by Julian Day in Appendix A. During 1983 operations, the remote installed at Station 01 was code 76, serial number 3004. Remote 74, serial number 3003, was installed at Station 02. During the 1984 season, remote 84, serial 3003, was installed at station 01 and remote 86, serial 3004, was installed at station 02. Del Norte codes were changed to 80 series during 1984 to eliminate interference from other users.

Five baseline calibrations were performed during this survey. All baseline calibrations were conducted in the immediate work area and entirely over water in accordance with AMC OPORDER 79. Baseline calibration distances were determined by the HP 3800A electronic distance measuring instrument, serial number 0987A00157. The following is a list of the baseline calibrations, as measured by the HP 3800A:

Date	Location	Ranse	
27 August, 1983	Belle Terre Bea Port Jefferson		
30 October, 1983	Pier 4S, NUSC, to S, Groton Je	New London, CT 2312.0m	
15 November, 1983	Pier 45, NUSC, to S. Gratan de	New London, CT 2312.0m	

28 September, 1984

Newport Naval Pier 2 to Gould Island S.E. Pier

1933.2m

29 October, 1984

Pier 48, NUSC, New London, CT 2312.0m to S. Graton Jetty

Daily calibrations were conducted in the vicinity of the entrance to New London Harbor usins three point sextant fixes with check angles. The daily system checks or calibration correctors were computed using a HP 9815A computer S/N 1825A02388 and the Hydro Calibration Package program. These daily correctors and baseline calibration data are available in Appendix A.

The daily correctors for all calibrations conducted during 1983 were stable and within accuracy tolerances for a survey of this scale. Therefore, only the baseline calibration data should be applied to the raw position data during final processing and smooth plotting of this data. Concur

Durins 1984 operations, Del Norte failures required switchins DMU/MASTER pairs on the HECK according to the following scenario. On UD 290, DMU/MASTER 142/3033 was used. On UD's 296-298, 145/3014 was used and en UD 300, 142/3014 was used. Accordingly, only open baseline calibration data is available for combinations 142/3033 and 145/3014. Combination 142/3014, used on UD 300, only had a closing baseline calibration conducted on UD 303. However, all units had daily calibration checks conducted prior to and after survey operations, when the systems were operational. Since these daily checks were all well within acceptable standards, only available baseline calibration data should be applied during final processing of 1984 data. Company

H. Dates of Survey

This survey was besun on 26 October, 1983, (JD 299) and was completed on 26 October, 1984, (JD 300).

I. Reduction and Processins of Data

All side scan sonar data was initially recorded in NOAA Form 77-44, Sounding Volumes. All header data, position numbers, time, and position control data were recorded in the appropriate columns in the volumes. The remarks column was used to record all line information, vessel rpms, lensth of tow cable (measured from the waterline to the towfish), vessel heading, and any other unusual or noteworthy remarks. The towfish layback was computed by adding the amount of tow cable out the stern plus the stern to antenna distance.

Position data from the side scan sonar work was entered in the Disital PDP 11/34 computer with a modified version of the R/H Double Precision Wire-Dras program. Rates for just one vessel were entered in this program and a single vessel position plot was then generated with the Houston Instruments roll-bed plotter. All side scan sonar work for this survey was plotted in this manner. The 1983/84 versions of the Rude and Heck wire dras programs were used to plot all data on this field sheet.

Side scan sonar coverage was computed and listed on the Side Scan Sonar Coverage Abstract, see Appendix L. The required 100% side scan sonar coverase was obtained within all areas of the corridor.

The sonargrams from the side scan sonar work were examined while on line and then again at the end of the day. notable contacts were flassed durins each examination. flassed contacts were then lossed in the Side Scan Sonar Tarset Abstract for that field sheet. The Target Abstract was then completed and the contacts were plotted on the smooth sheet containing the vessel position plots. The towfish layback was computed by adding the length of towcable out the stern plus the stern to antenna distance (21.3m). However, it should be noted that this layback value is an estimated value used for plottins purposes only. Since a K-Wins depressor was used, the actual larback was somewhat less than the value used, which was computed by adding the antenna to stern distance plus the towcable length. The layback and ranse to tarset values from this list were the distances used to plot the contact positions. All values of towcable length on the sonargram and in the sounding volumes refer only to the amount of cable out from the waterline to the towfish. The Side Scan Sonar Tarset Lists were then compiled from the Target Abstracts and the contact plots. The Del Norte rates of the contact positions were determined using a grid and overlay. These rates were then used to determine the latitude and lonsitude of the contact with the HP 9815A computer and the Geodetic Packase program.

J. Junctions and Splits

- FE-268 WD

(This survey junctions to the west with contemporary FF-26455 survey R/H 20-14-83/84 and to the east with contemporary survey R/H 20-16-84. There is adequate overlap with both surveys R/H 20-14-83/84 and R/H 20-16-84 - See the Evaluation Report, section 5.

K. Comparison with Prior Surveys

All R/H 20-15-83/84 side scan sonar and wire-dras records were compared to prior surveys H-9212. H-8709, and H-8926. In seneral, the sonar records, sounding records and wire-drag clearance data from this survey compare favorably with these Prior surveys.

In particular, the two significant peaks on the prior survey H-9212 at 41-13-50 N. 072-06-55 W and 41-14-05 N. 072-06-45 We are rather dramatically presented on the sonarsram as contacts 34.35.38.45 and 11.22.23, respectively.

There were several rocky areas and areas of boulders

noted on the sonardrams that are not indicated on the prior surveys. One boulder field was noted covering a fairly large area from 41-14-00 N; 072-03-10 W to 41-14-45 N; 072-03-45 W; including contacts 2; 13; 14; and 16. The other rocky area was centered around 41-13-40 N; 072-07-40 W; in the vicinity of contacts 42-44. The entire area in the vicinity of Valiant Rock; 41-13-35 N; 072-04-04 W; is composed of numerous boulders as indicated on the prior survey. - These areas are portrayed on the "Area of Side Scan Sonor Coverage" chart section included at the end of this report.

A comparison was made with NOS charts 12354, 13212, 12372, 13205, and 13209. The most comprehensive comparison was made with chart 13212, 29th Ed.; Jan 1/83, since the chart is also 1:20,000 scale and covers a common area. In seneral, the soundings and sonar records from this survey compare well with the chart.

Resarding non-sounding features, the following charting recommendations are offered:

1. Chart "Tide Ries" at 41-14-40 N, 072-03-10 W, and 41-13-42 N, 072-04-00 W.- Concur.

2. Chart "Blds" at 41-14-25 N, 072-03-40 W; 41-18-42 N, W.- Concur

All floating aids to navigation were checked during the course of this survey. All aids are correctly charted and are suitable for the purpose for which they were intended.

*3. Chart "Rky" at 41-14-25 N, 072-02-45 W.-Concur

In addition, the charted obstruction swept by wire drag to 23 feet, at 41-16-26 N, 072-02-39 W, was searched for during a sonar investigation on JB 294, 1983, but could not be located. It is recommended that a disproval investigation be conducted on

It is recommended that a disproval investisation be conducted on this item when practical bear included with this survey and therefore no recommendations are made by As reported in the June 1984 Monthly Activities Report, the charted tank at Seaside, Conn., at 041-18'-13.034"N, 072-07'-57.667"W; has been dismantled and should be removed from all affected charts. A copy of the supporting chart section and form 76-40 has been included in Appendix J, Dansers to Navisation Report. All other presently charted landmarks in the proximity of this survey were visually verified from offshore and are adequate for charting. SEASIDE SANITARIUM ELEVATED TANK, 1932.

The shoreline contained within the limits of this survey is from chart 13212, 29th Ed.. This shoreline is for orientation purposes only on the smooth, sheet. - See section 2. of the Evaluation Report.

M. Adequacy of Survey

All sections of the corridor on this survey were adequately covered by either side scan sonar or wire-dras operations. See sections L and N of this report for additional survey operation recommendations.

N. Incomplete Items

Rock, and 4, vicinity Race Rock, and 4, vicinity Race Rock, are the only contacts on this survey which would concern deep draft tanker traffic. However, given the proximity of both targets to marked and charted dangers, additional investigation of these items is not considered necessary.

An attempt was made to clear, by wire-dras methods, the two sisnificant reaks located at 041-18'-50"N, 072-06'-55"W, and

Do not concar - additional investigation in the vicinity of Race Rock is recommended. Target #1 is consistant with 6 prior data and future work on this target is not considered necessary. See the Evaluation Report.

041-14'-05"N, 072-06'-45"W, contacts 34,35,38,45 and 11,22,23, respectively. Contacts 38,11,22, and 23 were cleared in two directions to an effective depth of 72 feet. However, the extreme currents in this area appeared to be influenced by these peaks, resulting in extremely confused seas and currents setting north and south of these features. Review of the sonar records, and the least depth computations on these contacts, indicated that although these are significant hydrographic features, there is in excess of 150 feet of water over these items. No additional work on these items is warranted. In addition, this is a very difficult area to wire dras, posins potential dansers to both equipment and personnel. This area is well covered by prior surveys,

Contacts 8 and 16, in addition to the contacts identified above, should probably be further investigated during future hydrographic surveys. However, within the context of this survey with resard to clearing the tanker route, no further work is required. These contacts pose no threat to surface navigation and do not warrant further investigation on this basis, however future hydrographic surveys of this area should a. Currents and Winds

In seneral, the times and strengths of maximum current and times of slack water agreed with the predicted times and strensths under normal conditions. However, this entire area is sreatly influenced by the wind which results in nontidal currents which considerably prolons or reduce the tidal currents depending on wind direction and duration. See the previous section of this report for additional comments on currents.

P. Personnel

The officers participatins in this survey were LCDR Donald D. Winter, LCDR Robert K. Norris, LT Neal G. Millett, LT & Edward M. Clark, LT Joseph C. Talbott and ENS Thomas G. Callahan.

Q. General Notes

See the Coast Pilot Report and Loran-C comparisons for OPR-B660-RU/HE-83/84 and the Descriptive Report for OPR-B660-RU/HE-82 for additional information on this survey.

The format of this report is a composite of the Descriptive Report formats contained in the Wire Bras and Hydrosraphic Manuals. This format is the optimum composite of the pertinent sections of the two reports and is more applicable to the surveys currently being conducted by the Rude and Heck Concur

Chartins recommendations: - See also sections 6. \$ 7. of the Evaluation Report. 13-50 N, 072-04-00 W. - Concur at 41-14-40 N, 072-03-10 W, and 414 2, Chart "Blds" at 41-14-25 N, 672-08-40 W; 41-13-42 N 672-07-45 W; 41-14-35 N, 972-06-00 W; and 41-13-55 N, 072-04-00 W. - Concur

3. Chart "Rky" at 41-14-25 N. 072-02-45 W. - Concur

See section L for a complete chart comparison with this survey.

Respectfully submitted,

Med & Mor

Neal G. Millett, LT., NGAA

ATLANTIC MARINE CENTER
Hydrographic Surveys Branch
439 West York Street
Worfolk, Virginia 23510

N/MOA2321: MBH

Vice Admiral Paul A. Yost, USCG District Commander Third Coast Guard District Governors Island New York, New York 10004

Dear Admiral Yost:

Indications of two (2) uncharted shoals and an obstruction were noted during the office processing of NOAA's wire drag and side scan sonar field examination FE-262 WD, New York, Long Island Sound, The Race. These shoals and obstructions are considered dangers to navigation. Quastions concerning this survey may be directed to Mr. Maurice B. Hickson, III, Evaluation and Analysis Group, telephone (804) 441-6268 (FTS 827-6268).

The following text is recommended for inclusion in the Local Notice to Mariners:

"Uncharted shoaling in the form of a ridge extending from Race Rock south into The Race has been reported. Reported depths on this ridge are:

Thirty-two (32) feet at Mean Low Water in Latitude 41°14'31.0"N, Longitude 72°02'52.5"W. Fifty-four (54) feet at Mean Low Water in Latitude 41°14'28.5"N, Longitude 72°02'56.3"W. Seventy-seven (77) feet at Mean Low Water in Latitude 41°14'24.8"H, Longitude 72°02'48.9"W."

*Uncharted shoaling in the form of a ridge oriented north-south located approximately three hundred-fifty (350) maters east of Race Rock and extending into The Race has been reported. Reported depths on this ridge are:

Forty (40) feet at Mean Low Water in Latitude 40°14'32.7"N, Longitude 72°02'37.0"W. Fifty-five (55) feet at Mean Low Water in Latitude 41°14'29.3"N, Longitude 72°02'37.0"W."

"An uncharted obstruction extending approximately twelve and one-half (12½) feet off the bottom with a reported depth of twenty-five (25) feet at Mean Low Water has been reported in Latitude 41°14'30.0"N, Longitude 72°02'55.1"W."

3"wix^^P;g

INVALID COMMAND "Y". (LOGOSCP) LOGIN PLEASE. ER! LOGIN NMS

ANMS (USEP 14) LOGGED IN WEDNESDAY, 03 JUL 85 19:56:28. WELCOME TO PRIMDS VERSION 19.3.7. LAST LOGIN WEDNESDAY, 03:JUL 85 19:48:48. (1 OTHER USER UNDER THIS:ID.)

ENTER USER ID: KWH

WED, JUL 03 1985 WELCOME TO THE BUTOMATED NOTICE TO MARINERS

DK, SEG SANMS

- THE CUPPENT MOTICE NUMBER is 29/85 -

ENTER SELECTION NUMBER OR 98 TO DISPLAY SELECTIONS 10
THIS IS THE ANM SYSTEM MAILBOX
ENTER CODE OR PERSON MESSAGE IS FOR (20 CHAR MAX)
DMA/HTC
ENTER NAME OR ORGIN OF MESSAGE (20 CHAR MAX)
N/MOA2X1 (RLP)
ENTER REFERENCE, IF ANY OR RETURN (50 CHAR MAX)

ENTER MESSAGE TEXT (69 CHARACTERS PER LINE)
BELOW THE LAST LINE OF YOUR MESSAGE
ENTER THE WORDS: MESSAGE STOP

THE THREE (3) DANGERS TO NAVIGATION REFERRED TO IN MESSAGE NUMBER 85-000905 AFFECT THE FOLLOWING MOAH CHARTS: 12372 SC, 13205,13209,AND 13212.

MESSAGE STOP

MESSAGE ENTERED IN THE SYSTEM MAILBOX SYSTEM ASSIGNED MESSAGE NUMBER 85-000906 NO TREE NAME... YOUR SPOOL FILE IS PRNT01

ENTER: SELECTIO

SELECTION NUMBER 98 TO DISPLAY SELECTIONS 99 TO TERMINATE PROGRAM

99

ANMS (USER 14) LOGGED DUT WEDNESDAY, 03 JUL 85 19:59:52. TIME USED: 00H 03M CDNNECT, 00M 05s CPU, 00M 04s I/D.

Charts affected are 12372 SC, 13205, 13209, and 13212.

A teletype message of these dangers has been sent to DMAHTC, Washington, D. C. (NVS).

Sincerely,

Wesley V. Hull RADM, HOAA Director, Atlantic Marine Center

CC: N/CG222

STOP

MESSHG

ANMS (USEP 14) LOGGED IN WEDNESDAY: Welcome to PRIMOS version 19.3.7. LAST LOGIN WEDNESDAY, 03 JUL 85 18:54:32.

ENTER USER ID: KVH

WED, JUL 03 1985 WELCOME TO: THE AUTOMATED MOTICE TO MAPINERS

DK, SEG #AMMS

THE CURRENT NOTICE NUMBER IS 29/85

ENTER SELECTION NUMBER OR 98 TO DISPLAY SELECTIONS THIS IS THE ANM SYSTEM MAILBOX ENTER CODE OR PERSON MESSAGE IS FOR (20 CHHR MAX) DMAZHTC ENTER NAME OR ORGIN OF MESSAGE (20 CHAR MAX)
N/MOA2X1(LP)
ENTER REFERENCE, IF ANY OR RETURN (50 CHAR MAX) MOA 2321 MMO DATED JULY

ENTER MESSAGE TEXT (69 CHARACTERS PER LINE) BELOW THE LAST LINE OF YOUR MESSAGE ENTER THE WORDS: MESSAGE STOP

THE FOLLOWING DANGRS TO NAVIGATON WERE DISCOVRED DURING THE GENERAL AREA OFFICE POCESSING OF AN NOS SURVEY. OF HE DANGERS IS THE ACE?? OF THE DANGERS IS THE RACE, LONG ISLAND SOUND, NEW YORK.

- UNCHARTED SHOALING IN THE FORM OF A RIDGE EXTENDING FROM. RACE ROCK SOUTH INTO THE RACE. DEPTHS ON THIS RIDGE ARE: THIRTY TWO (32) FEET AT MLW AT LAT 41-14-31.0√N, LONG FIFTY FOUR (54)/ FEET AT MLW AT LAT 41-14-28.5N, 3 W. SEYNTY SEVEN (77)/FEET AT MLW AT LAT 72-02-52.5/W. LONG 72-02-56.3 W. 41-14-24.8/N, LONG 72-02-48.9 W.
- 2 UNCHARTED SHOALING IN HE FORM OF A RIDGE ORIENTED NORTH-SOUH AND LOCATED APPOXIMATELY THREE HUNDRED FIFTY (350) METRS EAST OF RACE ROCK AND EXTENDING INTO THE RACE. DEPTHS ON THE RIDGE ARE: FORTY (40) FEET AT MLW AT AT 0-14-32.7 N, LONG 72-02-37.0 W. FIFT FIVE (55) FEET AT MLW AT LAT 41-14-29.3, LONG 72-02-37.0 W. DEPTHS ON THS
- 3. AN UNCHARTED OBSTRUCTION EXTNDING APPROXIATELY TWELVE AND ONE ALF (12.5) FEET OFF HE BOTTOM WITH A REPORTED DEPTH OF TWENTY FIVE (25) FEET AT MLW AT AT 41-14-0.0 N, LONG 72-02-55.1 W. //

?? POSITION AGAIN IS: LAT 41-14-30.0'N, LUNG 72-02-55.1'W.

LATITUDE FOR 40 FOOT DEPH ??

LATITUDE FOR 40 FOOT DEPTH IN DANGER NO. 2 IS 40-14-32.7 N. 🗸

THIS INFORMATION HAS BEEN FORWARDED TO THE THIRD .. C.G. DISTRICT IN NEW YORK.

LATITUDE FR

APPROVAL SHEET

R/H 20-15-83/84

Field operations contributing to the accomplishment of this survey were conducted under my supervision with frequent personal checks of progress and adequacy. This report and field sheets have been closely reviewed and are considered complete and adequate for charting.

See also the Evaluation Report.

Robert K. Norris

LCDR., NOAA

Commanding Officer

NOAA Ships RUDE & HECK

C. HORIZONTAL CONTROL

No new stations were established for this survey. See Appendix D, Signal List, for a complete listing of all stations used on this survey.

D. SIGNAL LIST

OPR-8660-ROME-84

SIGNALS/STATIONS

TOWER (1972)

ID MBR 1
LAT 411520.647
LON 720035.153
ELEV'N 49.00 M

WATCH HILL LTUSE,

ID NBR 2
LAT 411213.646
LOH 7 132.552
ELEVIN 18.50 F

BARTLETT REEF LT.

1D MBR 3 LAT 411627.924 LON 720815.740

FILE.

NEW LONDON HARBOR LIGHTHOUSE (1835)

ID NBR 4 LAT 411859.489 LON 720524,855

NEW LONDON LEDGE LIGHTHOUSE (1932)

ID NBR 5
LAT 411820.7932
LON 720440.5132
ELEV'N 17.70 M

SEAFLOWER REEF LT.

ID NBR 6
LAT 411745.245
LON 720201.462

NORTH DUMPLING LTHSE. (1874)

LATIMER REEF LINGS.

ID NSR 8 LAT 11815.871 LOH 13601.684 FILE 8

RACE ROCK LITHSE.

ID MBR 9
LAT 411436.1582"
LON 720251.414"

LITTLE GUIL ISLAND

FISHERS SS. CG CUPQLA (1934)

ID NER 11 LAT 411658 787 LOW 715641.848

SAYBROOK LTHSE.

1D NBR 12
LAT 41,1616.894
LON 722037.0189
ELEV'N 21.60 M

FILE

Seaside Sanitarium Elev. Tank (1932) ID NBR (USED DURING Bartlett Reaf Lt. FILE (Listed Seaflower Reef Lt. FILE

E. PNEUMO DEPTH GAGE CALIBRATIONS NEGATIVE REPORT

F. DIVING REPORTS

NEGATIVE REPORT

H. LOCAL NOTICE TO MARINERS REPORT

NEGATIVE REPORT


A Notice to Moriners will be generated by A.M.C. noting the two uncharted ridges in the vicinity of Race Rock and Target # 4.

J. DANGERS TO NAVIGATION REPORT

See the aforementioned note on Appendix H. - Local Notice to Mariners Report

A-63

,	RESPONSIBL	E PERSONNEL	
TYPE OF ACTION	T		
OBJECTS INSPECTED FROM SEAWARD	R. K. Norris, LCDR.,	NOAA	ORIGINATOR PHOTO FIELD PARTY HYDROGRAPHIC PARTY GEODETIC PARTY OTHER (Specify)
F-0511 IONS DETERMINED AND/OR VERIFIED			FIELD ACTIVITY REPRESENTATIVE
			OFFICE ACTIVITY REPRESENTATIVE
FORMS ORIGINATED BY QUALITY CONTROL AND REVIEW GROUP AND FINAL REVIEW ACTIVITIES	-		REVIEWER QUALITY CONTROL AND REVIEW GROUP REPRESENTATIVE
		R 'METHOD AND DATE OF LOCATION' Detric Instructions No. 64,	
OFFICE		FIELD (Cont'd)	
1. OFFICE IDENTIFIED AND LOC Enter the number and date day, and year) of the pho identify and locate the EXAMPLE: 75E(C)6042 8-12-75	e (including month, otograph used to	B. Photogrammetric fie entry of method of date of field work	eld positions** require location or verification, and number of the photo- te or identify the object.
I. NEW POSITION DETERMINED C Enter the applicable data F - Field P - F L - Located Vis - V - Verified 1 - Triangulation 5 - F 2 - Traverse 6 - T 3 - Intersection 7 - F	a by symbols as follows: Photogrammetric - Visually Field identified Theodolite Planetable Sextant ire entry of method of	angulation station is Rec.' with date of re EXAMPLE: Triang. Rec 8-12-75 III. POSITION VERIFIED VIS Enter 'V+Vis.' and da EXAMPLE: V-Vis. 8-12-75	d which is also a tri- s recovered, enter 'Triang. ecovery. :. GUALLY ON PHOTOGRAPH ste.
8-12-75 *FIELD POSITIONS are determin vations based entirely upon	•	**PHOTOGRAMMETRIC FIELD PO entirely, or in part, up by photogrammetric metho	on control established



L. SIDE SCAN SONAR COVERAGE ABSTRACT - TARGET ABSTRACT - TARGET LIST

			Sunar	Coverag	e Abstrac	<u>.</u> +	C	1112-B660-1	Ru/He-83	Then Ha	R/H 20-15-83
Cearch Track Humber	Sc	ماو ما	Minimum Tourish Height (m)	Minimum Effection Sconning Rosce (m)	Search Trock Humber	S_{co}	س) اق رئاج	Marineran Tout to Height (re)	Minimum Effective Scenning Tonge (m)	Marinum Track Specifical	Conservey. Analysis
119-107	20	04	42 m	200m	37-28	20	0 m	19	188 m	325	100%
108-104			/3	129	169-161			12	/19	290	
169-161			12	/19	28-24		·	19	188	175	100%
37-25			19	188	76-59			24	200	3/0	100%
25-20		· · · · · · · · · · · · · · · · · · ·	6	59	19-13			16	158	300	< 100 %) 100% with 411+ 582-58
A-82			:								100% with 411+ 582-587
76-58	:		24	200	57-43			38	200	3/0	1007
18-13			16	158	43-38			33	200	280	100%
57-38			33	200	17-103			28	200	375	100%
77-103			28	200	141-120			27	200	300	100%
141-128			27	200	552-539			20	198	250	100%
128-125			39	200	12-08			27	200	200	100%
126-120	20	0 m	30	200	581-572	20	0 m	32	200	260	1007.
T ,		·•								-	

	÷	C .	C:					*	Page 2 of 2
	· .	Jonar . [je Abstr.	ngt (OFR-B660-	Ru/He-83	Tien Ho	R/H 20-15-8
Search Track Honter	Pange Scale (a)	Minimum Tourish Height (m)	Minimum Elfection Sconning Rouge (m)	Search Trock Humber	Range Scole (m)	Minimum Too fish Height (m)	Minimum Effective Sconning Toine (m)	Maximum Tract Specifus	Conecay Analysis
552-539	200 m	20m	198	5/8-538	200m	22 M	200 m	375m	1007
521-536	i	35	200	144-151	<u> </u>				,,,,,
5/8-521		49	200	517-515		30 45	200	300	100%
144-151	1	30	200	515-504		18	178	240	100%
P 8 01-04		1//				<u> </u>			
12-08		27		504-501		20	200	270	100%
,		41	200	02-07		/2	119	310	100%
581-579		32	200	561-563		57	200	300	10.5
579-572		32		159-153		30	200	325	100%
159-153	·	30	200	563.571		36	200	240	100%
600	200				· · · · · · · · · · · · · · · · · · ·				
561-571	200 m	36	200	560-553	200 n	27	200	280	100%
					The second se		· · · · · · · · · · · · · · · · · · ·		

SIDE SCAN TARGET ABSTRACT

OPR-B660-Ruffe-83 DATE L, SAYBROOK LIGHTHOUSE RIH 20-15-83 L2 NEW LONDON LEDGE LIGHTHOUSE SHIP

			12 100			LEAS/						UCTOUT	RANGE	WIDTH	TOWFISH
TARGET	J.D.				LENGTH	REDUCED	CHARTED	HEIGHT	D2	R3	R4	HEIGHT	OF TARGET	OF TARGET	
NUMBER	TIME	FIX	COMPUTED	TOW	OF TOW	DEPTH	DEPTH	OF FISH				(M/PT)	(M)	(M/F T)	(M)
	UCT	#	RATES	SPEED	(M)	(FT)	(FT)	R1 (M)			1 1				
/	299	04-	R, 23700		9.1	87.1	94	17.0	63.0	64.0	73.0	2.1	61.2	1.0	30.4
	100	05	1, 8370		<u> </u>								12.01	NI	30.4
2	299	08	1 8380		9.1	311.2	320	79.5	99.0	102.0	106.0	3.0	62.8	4.6	30.7
	299	17-	2 . 388	 				Pasition Pla	t.f.R.	de					30.4
. 3	2//	18			9.1			/ω//		Ľ					30. 7
1,	299	24-	1, 24940		6.1	. , ,	,	7	8.5	90	100	3.8	7.4	1.1	27.4
4		25	1, 7540		6.1	32.5	45			1		3.0			
5	299	30	1, 2/3/5		22.00	• .	246	Depth of sp	ke fro	m tot	ю.				51.8
)		31.	12 7/85		30.5		.046.			<u> </u>	 			 	
6	299	3/-	R, 20710		30.5	260.3	277	63.5	135.0	1380	150.0	5.1	121.7	3.3	51.8
0	ļ.,	32	Rz 7420		30,5		2//	03.5	 		╁╌┈				-10
フ	299	12-	1. 19820		30.5	205.6	222	52.0	65.0	65.5	72.5	5.0	44.9	0.7	51.8
l	1.00	33	R. 22250	 			,		 	1	1	· .			ria
8	299	46-	1, 7600		30.5	173.3	194	66.0	104.5	105.0	1/6.0	6.3	85.7	0.6	.51.8
	299	67-	1. 20810	 				170	م د نشد	000	20	119	61.0	111	57.8
9	2//	68	12 7525	1	30.5	238.9	سيحور	67.0	87.0	88.0	720	4.9	07.0	1.4	37.0
10	299		 		13			Object in Colu	unte		*				51.8
10	277	73	1		30.5			Colu	mn	<u> </u>	/ /				37.0
	300	82-	1. 17800		20	210.5	ودد	65.0	93.0	160	102.0	3.8	70.0	3.9	51.8
11		83	12 8300	ļ	30.5		223			1	-	 			
12	300	·	1, 22840		30.5	214.4	237	53.0	/20.0	126.0	145.0	6.9	110.8	6.5	51.8
1/0	 	90	12 7620	 	 		 	 	1	-	100		10-	123	F10
1/3	300		R, 24025	1	30.5	204.8	216	50.0	193.0	95,0	1031	3.4	60.5	2.3	51.8
I———	300	93-	Rz 7880	 			 		· · ·	1,,,,	1,20		1020	2.2	51.8
14	300	94	Pz 7800		30.5	197.9	211	51.0	114.0	116.0	126.0	4.0	103.9	12.2	31.0
1	300	1:	10 2700	 	120 (1	21.0	53.0	541	580	1.6	49.3	1.1	57.8
15	1	7	1/2 9200	1	30.5	135.7	141	101.0	اررر	177.6	0.5	//0	1 /// /	1	1
	*		* No shadow		<	the	La llow	ins Si	des	Sca	n c	Sonar	Target	List.	
						ee me	101000	1	h			**	0.		
		7	* No shadow	observe	ed 0.1 50	nargram.	No height	computati	CH.						
		••		- 05 -		•		•							

SIDE SCAN TARGET ABSTRACT

J.D. OPR-B660-R1H--83

ITEM #

SHIP ____

	TARGET	J.D.	1			LENGTH	REDUCED	CHARTED	HEIGHT				HEIGHT	RANGE	WIDTH	TOWFISH
	NUMBER	TIME	FIX	COMPUTED	TOW	OF TOW	DEPTH	DEPTH	OF FISH	R2	R3	R4	OF TARGET	OF TARGET	OF TARGET	LAYBACK
	NOTIBER	UCT	#	RATES	SPEED	(M)	(FT)	(FT)	R1 (M)	(M)	(M)	(M)	(M/FT)	(M)	(M/FT)	(M)
	16	300	105-	R, 23700 R, 6840	OT BED	21.3	123.4	150		68.0	7/.0	92.5	8.1	62.5	3.2	42.6
	17	300	124-	R,		30.5			72.0	71.0	72.5	85.0	Object in Culumn	water		51.8
-	18	300	129	R, 22525 R2 78G0		30.5	156.8	164	32.0	93.5	96.0	/o3. 0	2.2	88.6	2.6	57.8
	19	300	1/33-	R, 20775 R ₂ 8300		30.5	273.4	298	78.0	ס.סבו	مددا	136.0	7.5	97.1	3.7	51.8
	20	300	133-	R, 20580 R, 8300		30.5	317.2	328	83.0	94.5	96.0	/0.0	3.3	50.8	2.7	51.8
	21	300	134-	R. 20360		30.5	314.5	326	78.0	176,0	177.0	182.5	2.3	158.9	1.1	51.8
	22	300	/35- /36	R, 19790 Nz 8520		30.5	213.6	231	62.0	94.5	96.0	105.0	5-3	75.6	1.9	51.8
	23	300	135-	e, 17730 e, 8415		30.5	141.0	223	60.0	65.0	67.0	115.0	25.0	54.8	2.4	51.8
	24	300	137-	R. 18980 Rz 8895		30.5	290.9	305	79.5	120.0	121.0	128.0	4.3	93.5	1.3	51.8
	25	300	138-	L, 18475- R, 9150		30.5	274.5	284	68.5	101.5	102.0	106,5	2.9	77.4	0.6.	51.8
	26	300	503	R, Rz	,	38.1		99	Pas. t. on Pla	+-Boo	lder	Field	1			59.4
	27	300	507-	K, 21100 K2 9010		38.1	317.1	326	70.0	131.0	134.5	140.0	2.7	112.4	4.1	59,4
	28	300	507- 508	R, 20990 Rz 9025		38,1	297.1	326	78.0	125.0	126.0	142.0	8.8	104.1	1.2	5-9.4
	29	300	507-	R, 20 950 R= 9.70		38.1	304.7	326	82.0	167.0	168.5	183	6.5	149.0	1.7.	59.4
	30	300	507-	R, 20900		38.1	249.8	281	83.0	/41.0	142.5	161.0	9.5	120.0	1.7	59.4

See the following Side Scan Sonar Target List.

A-8

SIDE SCAN TARGET ABSTRACT

OPR-<u>13660-RufHe</u>-83 R/H 20-15-83

ITEM #

SHIP

J.D.

DATE

LEAST

							LEAST				—т		HEIGHT	RANGE	WIDTH	TOWFISH
1	TARGET	J.D.				LENGTH	REDUCED	CHARTED	HEIGHT	20	R3	R4	OF TARGET	OF TARGET	OF TARGET	LAYBACK
- 1	NUMBER	TIME	FIX	COMPUTED	TOW	OF TOW	DEPTH	DEPTH	OF FISH	1 1		(M)	•	(M)	(M/FT)	(M)
İ	NOUBLK	UCT	#	RATES	SPEED	(M)	(FT)	(FT)	R1 (M)	(M)	(M)	(m)				-0
			57/-	R, 19300		307 1		23/	75.0	1285	129.0	137.0	4.4	107.3	0.6	59.4
- 1	31	200	512	Rz 9520		38,1	216.6							1210	2 7	59.4
١	```	300	515-	R. 17760		20.	200.4	207	47.0	130.0	132.5	138.0	1.9	121.9	2.7	37.7
	3,2		5/6	Rz 10050		38.1	200.1			1	. 18. A	ICO O	2.1	132.6	2./	59.4
	33	300	520-	R, 17760		38./		-207	53.0	142.0	144.0	120.0	2.1	100.6		3"/
	ر د	<u> </u>	521	12 10050		2017			Depto +		Fatho					59.4
	34	300	527-	R, 19640	1	38.1	1650	160	1 -	4	1		<u> </u>	ļ		
		20	578	R ₂ 8980 R, 19740	ļ	70.1	· .		Depth for	m Fa	tho.			·		59.4
	35	300	527-	K2 8950		38.1	1650	160	041	1	ļ		 		+	
		300	536-	R, 22625			·	107	36.0	99.0	101.0	*		93.0	12./	59.4
• .	36	300	537	12 8450	1	38.1		10/	130.0	 	 		 	1.	1	
3		300	536-	1, 22560				167	34.5	91.0	93.0	92.0	1.8	84.9	2.1	59.4
	37		537	2 8275		38,1	16[,1	<i>/</i> -	Depth to							59.4
		300	547-	R, 19485		38,1		192	We trace	Ime	10,-0	10	dale			137.7
	38		548	12 8809	ļ	120,1	 	 				1	1	121 -	2.3	59.4
		300	583-	1, 25100	1	38.1	175.5	187	75.0	191,0	434	7/30	3.5	121.5	10.5	10 7.7
	39		564	R, 8570	 	3011	 		-1.	120	1,,,,	1,	5.8	120.0	3.4	59.4
		300	578-	4 8500 4 8500	1	38.5	278.0	2.97	74.0	1381	141,0	133.	3.0.	1,00.0	+	
	40	+-,,	579 154-	2 8300	-	1 30.0			Hole in	ea bo	ttom	1	1	1		
	4	3//_	155	R,					17018	Ţ	-				1,	7.0
		308	145-	1. 18600		1,			43.0	500	51.0	57.0	4.5	31.9	1.5	51.8
	42	300	146	1 9575	ļ	30.5	194.2	209	175.0		+	+		1	2 /	51.8
		308	145-	R. 18730		200	213.1	222	50,0	67.5	-620	73.	0 2.7	48.2	2.1	31.0
	43		146	R2 9600	1	30.5	10.1	-				1		110.0	6.7	51.8
		308	145-	1. 18820	1	30.5		248	55.0	123.0	129.0	/ *		110.0	0.1	
	41		146	12 9625		+	 					7		1		51.8
	45	308	147	R 19745		30.5	153 C	150	see i	anth	F	om	Matho		, 	
	1 7 7	l	1 ' '	12 9035	1								PI	· · · < ·	10 500m	S

*No shadow observed on sonargram. No height computation.

... 4 ... 4

SIDE SCAN TARGET ABSTRACT

DATE______OPR-<u>B660-Ru//le-83</u>
J.D.____

ITEM #

SHIP

				1 7	I t macomit	REDUCED	CHARTED	HEIGHT				HEIGHT	RANGE	WIDTH	TOWFISH
TARGET	J.D.	777	COMMITTED	TOW	LENGTH OF TOW		DEPTH	OF FISH	R2	R3	R4	OF TARGET		OF TARGET	LAYBACK
NUMBER	TIME	FIX	COMPUTED RATES	SPEED	(M)	(FT)	(FT)	D1 (M)	(M)	(M)	(M)	(MLPT)	(M)	(M/PT)	(M)
46	J08	148	R. 20330	SPEED	30.5	2910	332	Depth 1	rom 7	Gth o					51.8
10 47	308	148-	l, 20880		30.5	262.0	28/	80.0	95.0	96.5	104.0	5.8	59.3	2.4	51.8
77		149	R, 8750			200.			<u>, </u>						
]	<u> </u>		· · ·		<u> </u>		 				<u> </u>		
						•					<u> </u>		·		
						ŧ									
		1													
			<u> </u>												
]	ļ		<u> </u>			 		├	-			<u> </u>	
		1							<u> </u>	ļ	1_	<u> </u>		<u> </u>	-
		-	-				·.								ļ
				ļ		1									
			ļ	ļ					 	-	†				
		1	<u> </u>	ļ	ļ	ļ	ļ		 	-	-	 	 		
		┪.								<u> </u>	<u> </u>				ļ
				 						1					
]	 	 		 		,	 	+-	+	 	1	†	
I		\dashv				1							<u> </u>		

O Predicted Tide Reducer Not Available To Be Applied

See the following Side Scan Sonar Target List.

A-8

OPR-<u>BGGO-RU/HE</u>-83 SHEET <u>R/H</u> 20-15-83

SIDE SCAN SONAR TARGET LIST

					2106	SCAN SUNAR TARGE	1 L131			•
			LEAST							
	TARGET	CHARTED	REDUCED	HEIGHT OF	WIDTH OF		FURTHE		TIGATION	
-	NUMBER	DEPTH (FT)	DEPTH (FT)	TARGET (FT)	TARGET (FT)	POSITION	TYPE	DATE	RESULTS	REMARKS
						Q 041-13-51.4				Investigate during future
	/	94	87.1	6.9	3.3	× 072-03-57.5				hydrographic project
			_			D 041-13-57.1				
	2	320	311.2	9.8	15.1	1 072-03-14.2				No additional work recom.
						8			1 11 5 1	tion Propert, sections 6.57.
	3		POSITION PO	OT OF RI	DGE - Ditters	from what is shown of	n the fat	hograms	- See the Eval	ation Report sections 6.37.
						Q 041-14-29.7				Investigate during future
	4	45	32.5	12.5	3.6	X 072-02-55.2				hydrographic project
			Noted as a sp	ike no fathou	ram trace shows	Q 041-14-31.2	<i>i</i> ²	in tale	209 in orier	lepths of 250'
	5	246	a people on Side	Scan with a co	wible locat death	1 072-05-32.2	ct aff	XIMA I TIY	20.7 111 71101.0	No additional work recom.
			a person since	sian while po	Sible dest creptor	Q 041- 14- 27.7		· · · · · ·		
	C	277	260.3	16.7	10.8	1 072-05-59.3				n thung n n
						Q 041-14-29.8				
	7	222	205.6	16.4	ي. ج	2072-06-37.6	:			11 11 11
						Q041-14-14.7				Investigate during future
Î	. 8	194	173.3	20.7	2.0	× 072-04-55.1.				hydrographic project
Č	3					Ø 041-14-25.6				- I Will Control of the Control of t
	9	255	238.9	16.1	4.6	× 072-05-55.9				No additional work recom.
						8				
	10	Object in 4	vater column	þ		3				1 1 1
		- J				b 041-14-08.3			Cleared to	i ud.
	11	223	210.5	12.5	12.8	× 072-06-43.8	W.D.	10/84	72 FT	
-						Q 041-14-13.9				
	12	237	214.4	22.6	21.3	1 072-04-29.6				No additional work recom.
						0 041- 14-09.6				
	13	216	204.8	11.2	7.5	× 072-03-39.0				11 11 11 11
			7,0 3,0		· · · · · · · · · · · · · · · · · · ·					
	14	211	197.9	13.1	7.2	041-14-14.1		ŀ		11 11 11 11
	7 7		,,,,,	ļ	/	λ 072-03-27.3				
į	15-	141	135.7	5.3	3.6	\$ 041-14-18.1		1		п п п
- 1		- ' '	237	3/3		× 072-00-50.7		 		Investigate during future
	16	150	123.4	26.6	10.5	0 041-14-42.8		ł		hydrographic project
		/	123.7	~ 6.6	, , , ,	λ 072-03-46.6·				TIVE OF SPILE PLOTECO
	17	Object in wat	er column			ام				
- 1			1	1	i	1^	l	ı		l

OPR-**8660-RV/HE-83** SHEET <u>R/H 20-15-83</u>

SIDE SCAN SONAR TARGET LIST

		LEAST			- COLLY CONTACT PRINCIP	31 3101			~ :	• "	
TARGET	CHARTED	REDUCED	HEIGHT OF	WIDTH OF		FURTH	ER INVES	STIGATION	1		-
NUMBER	DEPTH (FT)	DEPTH (FT)	TARGET (FT)	TARGET (FT)	POSITION	TYPE	DATE	RESULTS		REMARK	S
18	164	156.8	7. Z	8.5	\$ 041-14-06.0 ≥ 072-04-45.2				No additions		
11	298	273:4	24.6	12.1	\$ 041-13-59.1 \$072-06-03.6	W.D.	10/84	Cleared to 72 FT			
20	328	. 317-2	10.8	8.9	\$ 041-14-00.7 \$ 072-06-11-7	W.D.	10/84	Cleared to 72 FT			
رد	326	314.5	7.5	3.6	\$ 041-13-57.5 \$ 072-06-22.2	W.D.	10/84	Cleared to	72 FT		
22	23/	213.6	17.4	6.2	X 041- 14-01. 2 X 072-06-46.2	W.D.	10/84	Cleared to 72 FT		-	
23	ودد	141.0	82.0	7.9	\$ 041-14-05.4 \$ 072-06-47.7	W.D.	10/84	Cleared to 72 FT			
24	3050	290.9	14.1	4. 3	à 041-13-59.6 à 072-07-22.4	W.D.	10/84	Cleared to			
25	284	274.5	9.5	2.0	\$ 041-13-58.8 \$ 072-07-44-9	W.D.	10/84	72 FT	,		
عد	99	POSITION	PLOT BON	DER FIELD-	* Least depth by fat	hometer=	- 79'/vel	scity not applied	<i>prior depthis</i> No additiona	81'(H	-8709) recom.
27	326	317.1	8.9	13.5	D 041-13-34.4 h 072-05-56.7				11 11	,tt	11
28	326	297.1	28.9	3.9	Q 041- 13- 34.7 \ 072-06-01.5				11 : 11	11	11
9	مدی	304.7	21.3	5.6	Q 041-13-33,6 ≥ 872-06-03.6				11 11	Ħ	11
30	رود	249.8	31.2	5.6	× 041-13-42.4 × 072-06-03. 0				tt tt	11	11
3/	23/	216.6	14.4	2.0	0 041-13-35.4 \(\lambda\) 072-07-16.2				11 - 11	11	11
2,33	207	200.4	6.6	7.9	à 041-13-41.4 à 072-08-22.6				tt · tt	11	11
34	160	Uncorrected fatho.depth			Q 041-13-48.4 \(\lambda\) 072-06-56.7				Investigate o		
35-	160	Ancorrected fatho. depth 165			Q 041-13-48.3 > 072-06-52.4				W W	H	#

OPR-<u>BG60-RU/HE</u>-83 SHEET <u>R/H 20-15-83</u>

SIDE SCAN SONAR TARGET LIST

	_	LEAST				FURTHE	R TNVF	TIGATION	
TARGET	CHARTED	REDUCED-	HEIGHT OF	WIDTH OF	POSITION	TYPE	DATE		REMARKS
NUMBER	DEPTH (FT)	DEPTH (FT)	TARGET (FT)	TARGET (FT)	\$ 041-13- 46.9	1111	Dille	1.0000	
		Wot able to com	wite-height-groupot	rocks or simell hids.	× 012-04-45.8		Ì		No additional work recom.
36	107	in 161' depths		6.9	\$ 041-13-52.6		 		
			- ~	6.9	× 072-04-47.1		1		11 11 11
37	167	161.1	5,9	3.7	\$ 041-13-55.8	 		Cleared to	
	100	approximately			1 072-07-01.4	W.D.	10/84	72 FT	
38	192	200'			9 041-13-54.5				ar a data and areas more
مور	187	175.5	11.5	7.5	1 072-02-55.6				No additional work recom.
127	/6/	1//3/3	7773		Q 041-13-58.5				n n n
40	297	271.0	19.0	11.2	1 072-02-48.8				
40					R		1	1	11 11 11 11
41		Hole in Se	a bottom	_	λ	<u> </u>	ļ		
ļ		77.00			Q 041-13-43.2	1			m m m
42	209	194.2	14.8	4.9	1 072-07-44.5	 		<u> </u>	
1					Q 041-13-40.5				n n n
43	222	. 2/3./	8.7	6.9	× 072-07-39.7		+	 	., ,, 11 11
-		No shadow, the	efore no hoight		b 041-13-38.4				n n n
44	248	Varant in 253 Uncorrected +	depths	0.66	1 072-07-36.4		+		Investigate during future
		Uncorrected +	Patho depth	!	à 041-13- 45.5 à 072-06-53.0		-		hydrographic project
45	129	154'	1	<u> </u>	A 041- 13-46-4	 	 		
	332	Uncorrected	fatho.depth		λ 072-06-26.9	ļ	İ		No additional work recom.
46	332	Z92'	ļ		Q 041-13-44.1				
1-	281	262.0	19.0	7.9	X 072-06-03.4				ii ii ii ii
47	001	202.0	17.0	+	7				
							<u> </u>		
	 	+	+					1	
	1		1						
	 	-	1				1		
	1								
		 							
							+	 	
				1		1			
	•	1	<u> </u>						

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SERVICE

TIDE NOTE FOR HYDROGRAPHIC SHEET

Date: 04/26/85

Marine Center: Atlantic

OPR: B 660

Chart Evaluation Survey: FE-262, R/H-20-15-83/84

Locality: Long Island Sound Entrance

Time Period: October 1 - December 31, 1983

Tide Station Used: 846-1490 New London, CT

Plane of Reference (Mean Low Water): 3.54 ft.

Height of Mean High Water Above Plane of Reference: 2.6 ft.

Remarks: Recommended Zoning:

- 1) Southeast of a line formed by two points located at latitude $41^{\circ}12.4'$ and longitude $72^{\circ}06.4'$ and latitude $41^{\circ}15.0'$ and longitude $72^{\circ}02.4'$ apply -15 minute time correction and x0.89 range ratio to all heights.
- 2) Northwest of the previous line, zone direct.

Chief, Tidal Datums Section

DATE: 12/19/84

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SERVICE

TIDE NOTE FOR HYDROGRAPHIC SHEET

Marine Center: Atlantic

OPR: B660

Hydrographic Sheet: R/H 20-15-84 FE - 262 WD

Locality: Long Island Sound Entrance

Time Period: October 16-26, 1984

Tide Station Used: 846-1490 New London, CT

Plane of Reference (Mean Lower Low Water): 3.54 ft

Height of Mean High Water Above Plane of Reference: 2.6 ft

Remarks: Recommended Zoning;

- 1) Southeast of a line formed by two points located at latitude 41° 12.4' longitude 72° 06.4' and latitude 41° 15.0' longitude 72° 02.4', apply a -15 minute time correction and x 0.89 range ratio to all heights.
- 2) northwest of the previous line zone direct.

Chief, Tidal Datums Section

NOAA FORM 76-155 (11-72)	NATIONAL	CEANIC			ENT OF CO		SU	RVEY N	UMBER	
	GEOGRAPH							FE-262	WD	
Name on Survey	A	H CHART N	PREVIOUS P	U.S. MAPS	ANGLE OF ON OR OF OF	DA NA	P. G. EVIDE	OR MAP	S. LIGHT L	s ^t
LONG ISLAND SOUND	(title)✓									1
NEW YORK (title)			·							2
THE RACE (title)										3
RACE ROCK	✓									4
VALIANT ROCK										5
										6
										7
										8
										9
										10
										11
										12
										13
										14
										15
										16
										17
					Appro	ved:				18
					0					19
					Chr	۵- کو.	Har	wite		20
					Chief	Geogra	nhe r -	17/26	243	21
										22
					J	N 26	165			23
										24
				:						25

NOAA FORM 76-155 SUPERSEDES C&GS 197

NOAA FORM 61-29 U. S. DEPARTMENT OF COMMERCE (12-71) NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION	REFERENCE NO.
·	MOA 23 - 75 - 85
LETTER TRANSMITTING DATA	DATA AS LISTED BELOW WERE FORWARDED TO YOU BY (Check):
	ORDINARY MAIL AIR MAIL
то:	REGISTERED MAIL EXPRESS
CHIEF, DATA CONTROL SECTION HYDROGRAPHIC SURVEYS BRANCH, N/CG243 NATIONAL OCEAN SERVICE, NOAA	GBL (Give number)
ROCKVILLE, MD 20852	DATE FORWARDED
L .	July 3 1985 NUMBER OF PACKAGES
	Two (2)
NOTE: A separate transmittal letter is to be used for each type of da etc. State the number of packages and include an executed copy of the tion the original and one copy of the letter should be sent under se receipt. This form should not be used for correspondence or transmitting.	e transmittal letter in each package. In addi- parate cover. The copy will be returned as a
FE-262 WD R/H-20-15-83/84 OPR-	B660 - RU/HE - 83/84
New York, Long Island Sound, The Race	
Package # 1 of 2 (Tube)	
VI - Original Descriptive Report with one Smooth So AFD Sheet, and one Smooth Wire Drag Pos 11 - Final Field Sheet, containing all side-scan smat	jurding Sheet, one Smooth Wire Drag
A - Preliminary Field Sheets.	contacts and coverage.
12 - Field Wire Drag Strip Plots. 16 - Office verified Wire Drag Strip Plots.	• .
Parkers #2 of 2 (Park)	
12 - According Folders containing Echograms ar 12 - Sounding Volumes 12 - Wire Drug Volumes 12 - Fundamentains Side-Scan Sommeran	nd Field Data Printouts.
VI - Envelope containing Side-Scan Sonargran	<u>.</u> ,
VI-Envelope containing Side-Scan Sonargran 1-Envelope containing Smooth Tide Data and VI-Envelope containing Wire Drag Strip Printo VI-Envelope containing Data removed from the	Printents ets
1 - Envelope containing Data removed from the	Descriptive Report.
	,
·	
FROM: (Signature) Maurine B. Hicken The for LCDR David B. MacFarland, Tr.	RECEIVED THE ABOVE (Neme, Division, Date)
for LCDR David B. MacFarland, Jr.	Dwayne S. Clark
Return receipted copy to:	Duly he S. Vare
ATLANTIC MARINE CENTER	fuly 17, 1985 NICG 243.
HYDROGRAPHIC SURVEYS BRANCH (NIMOA23)	Rockville
439 W. YORK STREET NORFOLK, VIRGINIA 23510	roceville
L TOTAL VINGHAMA 233IU	
494 • •	· .

HYDROGRAPHIC SURVEY STATISTICS REGISTRY NO.: FE-262 WD

Number of positions		328
Number of soundings		N/A
Number of control stations		8
	TIME-HOURS	DATE COMPLETED
Preprocessing Examination	19	<u>June 14, 1985</u>
Verification of Field Data	32	June 18, 1985
Quality Control Checks	N/A	
Evaluation and Analysis	66	June 28, 1985
Final Inspection	4	June 27, 1985
TOTAL TIME	121	
Marine Center Approval		<u>June 28, 1985</u>

Transmittal letter of survey and survey records will be included in the Descriptive Report to identify the records accompanying the survey.

ATLANTIC MARINE CENTER EVALUATION REPORT

SURVEY NO.: FE-262 WD FIELD NO.: R/H-20-15-83/84

New York, Long Island Sound, The Race

SURVEYED: October 26, 1983 through October 26, 1984

SCALE: 1:20,000 PROJECT NO.: OPR-B660-RU/HE-83 &

1:40,000-Wire Drag Smooth Plot OPR-B660-RU/HE-84

SOUNDINGS: Raytheon DE-719B Fatho- CONTROL: Del Norte 520 meter, Raytheon DSF-6000N (Range/Range)

Fathometer, Klein Side-Scan Sonar, Wire Drag

R. K. Norris (1984)

.....J. C. Talbot

1. INTRODUCTION

- a. The purpose of this survey is to provide 100% side-scan sonar coverage over a portion of the Northville Industries Corporation oil tanker route and to provide wire drag clearances over contacts located by side-scan sonar which the hydrographer deems necessary to further investigate.
- b. This survey is a side-scan sonar and wire drag survey. Raytheon DE-719B Fathometers (1983) and Raytheon DSF-6000N Fathometers (1984) were operated concurrently with side-scan sonar and wire drag, but the soundings are of reconnaissance value only as all necessary sounding correctors were not determined. No hydrography beyond reconnaissance hydrography was required. No field plots or any data tapes were made for this hydrography.
- c. A standard smooth sheet (A&D) and accompanying position overlay were generated for the wire drag portion of this survey and are attached to this report. A smooth sheet containing six soundings was generated to show shoaler soundings in the vicinity of Race Rock than indicated on the prior surveys or the charts. No curves were drawn on this smooth sheet as inadequate information exists to delineate bottom configurations. No smooth plot was generated for the side-scan sonar portion of this survey since the final field sheet adequately displays the lines run and the contacts found. A chart section depicting the area insonified, the boulder fields found and the area described as rocky by the hydrographer is attached to this report.

d. Corrections and notes made by the Evaluator to the Descriptive Report are denoted in red ink.

2. CONTROL AND SHORELINE

- a. The source of control is adequately discussed in section F. and Appendix D. of the Descriptive Report.
- b. No shoreline was drawn on any of the smooth sheets. Charted shoreline is drawn on the final field sheet and the relationship of shoreline to the area surveyed is adequately shown on the attached chart section depicting the area of side-scan sonar coverage.

3. HYDROGRAPHY

The echo sounding hydrography collected on this survey are of reconnaissance value only. The soundings portrayed on the sounding smooth sheet are reconnaissance soundings and are considered unqualified soundings.

The side-scan sonar coverage is adequate and meets the requirements specified. See section 4.f., 4.h., and 6.a. of this report regarding the investigation of submerged ridges in the vicinity of Race Rock.

4. CONDITION OF SURVEY

The final field sheet, survey records, and reports are adequate and conform to the requirements of the HYDROGRAPHIC MANUAL and WIRE DRAG MANUAL with the following exceptions:

- a. In general the Descriptive Report is well written.
- b. Prior surveys common to the survey area which were identified in the Project Instructions were used for comparisons by the Hydrographer. The Project Instructions were deficient in that they did not list or require comparisons with prior surveys H-4008 WD (1917-18) and H-4008a WD (1917-18).
- c. Lift computations and lift and tide applications to field data were not in accordance with the WIRE DRAG MANUAL. Lifts were recomputed during verification. Lifts and smooth tides were applied to the verified data in accordance with the WIRE DRAG MANUAL during verification.
- d. Numerous gaps of data exist in the 1983 fathograms largely due to the inability of the Raytheon DE-719B to maintain a bottom trace in areas of deep bottom and very irregular bottom topography. Operator inexperience may have contributed somewhat in not being able to shift scales as rapidly as the bottom changed.
- e. Side-scan sonar contact analysis differs somewhat between field and office computations. These differences are due to individual interpretation of the contacts, the aging of the sonargrams between field and office analysis, and the sonargram portrayal of the contacts due to the depths encountered and towfish height above the bottom in the

deep and irregular areas. These differences between field and office computational analysis are not significant in the context of this survey since all but four of the designated contacts have least computed depths greater than 100 feet.

- f. The position of the ridge in the vicinity of Race Rock drawn on the final field sheet differs positionally from the portrayal of the peak of this ridge on the fathograms. Positioning of significant hydrographic features is more accurately achieved with the fathometer than the side-scan sonar with the former records permitting.
- g. The geographic positions of four signals listed in Appendix D. of the Descriptive Report contained slight discrepancies and were corrected during verification.
- h. No least depths on contacts were determined by conventional methods as required by section 7.12.3.1 of both the 1983 and 1984 Project Instructions. A number of contacts were cleared by wire drag as a conventional method to determine safe passage over the area. However, all but four (4) of the contacts are in water deeper than can be investigated by a diver and have computed least depths of over 100 feet, therefore, pose no threat to surface navigation. The remaining four (4) contacts (#1, #3, #4, and #26) are in an area of strong and dangerous currents which prohibit diving and wire drag. Contacts #1 and #26 agree reasonably well with prior hydrography and further investigation is not recommended.

A basic hydrographic development of contacts #3 and #4, particularly the ridges in the vicinity of Race Rock would have provided valuable data for charting. This was not a requirement in the Project Instructions, however, the chart is deficient in this area and the RUDE and HECK were vessels of opportunity. Additionally, the ridge east of Race Rock was not noted in this survey by the hydrographer.

5. JUNCTIONS

Adequate junctions exist with FE-268 WD (1983-84) to the west and FE-264 SS (1984) to the east. Adequate side-scan sonar overlap exists between the present survey and the aforementioned junctional surveys. The present survey wire drag areas are common to some of the junctional area of FE-268 WD (1983-84) and clear the junction survey contact #1 by 72 and 79 feet (opposing directions). FE-268 WD (1983-84) contact #1 is common to the present survey but was not detected since it is directly under a line and therefore the side-scan sonar did not detect it, and the fathogram for that line has a gap with no coverage over this contact. Contact #1 is not considered of any significance since its height is approximately 7.5 feet and it lies in depths of approximately 270 feet. Contacts #32 and #33 on the present survey are contacts #8 and #30 on FE-268 WD (1983-84). Present survey contacts #24, #25, #31, #32 & #33, #42, #43, and #44 were cleared in one direction by a field effective depth of 76 feet by wire drag on FE-268 WD (1983-84).

Adequate wire drag junctions exist between FE-268 WD (1983-84) and the present survey. This junction will be portrayed on FE-268 WD (1983-84) when it is processed.

Present survey contact #15 (PA) was noted in a turn after the line broke and is common to junctional survey FE-264 SS (1984). This contact was not detected by FE-264 SS (1984) and is not considered a significant contact since it has a computed target height of 5.3 feet and lies in depths of approximately 141 feet.

No contemporary surveys exist to the north or south of the present survey.

6. COMPARISON WITH PRIOR SURVEYS

a. Hydrographic Surveys

H-8709 (1961-62) 1:20,000 H-8926 (1966-68) 1:10,000 H-9212 (1971) 1:20,000

These prior surveys cover the entire area of the present survey and are the source for all charted hydrography except for two soundings within the common area which are a charted 265-foot sounding in Latitude 41°14'44.0"N, Longitude 72°05'46.5"W, and a charted 95-foot sounding in Latitude 41°14'32.0"N, Longitude 72°01'32.5"W, These two soundings fall exactly on soundings gathered by the prior surveys with the charted 265-foot sounding being where a prior sounding (H-9212) is 285 feet and the charted 95-foot sounding being where a prior sounding (H-8926) is 96 feet. It is suspected that these are compilation errors rather than soundings originating from other sources. No conflicts exist between prior hydrography and present wire drag effective depths.

Side-scan sonar contacts within the common area range from 5.3 feet to 31.2 feet above the bottom. Only four contacts (#1, #3, #4 and #26) have computed least depths shoaler than 100 feet.

Contact	Latitude	Longitude	Prior Survey Depth	Estimated Least Depth of Contact
#1	41°13'51.5"N	72°03'57.3"W	94'	87'
#3	41°14'24.8"N	72°02'48.9"W	124'	77'
#4	41°14'30.0"N	72°02'55.1"W	45'	25' -
#26	41°13'42.6"N	72°04'26.2"W	81'	79 '

Other than in the vicinity of Race Rock, adequate comparisons between prior hydrography and present reconnaissance hydrography are made by the hydrographer in section K. of the Descriptive Report.

In the vicinity of Race Rock, two ridges extend south into The Race which are not portrayed on the prior surveys. Five reconnaissance soundings were selected on the peaks of these ridges and are plotted on the sounding smooth sheet included in this report with an estimated least depth of contact #4. A Notice to Mariners noting these two ridges and contact #4 will be generated by AMC. One ridge extends south from Race Rock and the other ridge runs approximately north-south, and is approximately 350 meters east of Race Rock. Three (3) of the five (5) reconnaissance soundings were gathered in 1983, and the other two (2) in

1984, which may explain why the 54-foot sounding (1984) in Latitude 41°14'28.5"N, Longitude 72°02'56.3"W, is not in alignment with the 32-foot and the 77-foot soundings gained in 1983 on the ridge extending south from Race Rock as this ridge may be migrating due to currents, storms, and seasonal changes. These ridges are not charted and the extent and shoalest depths could not be determined from this survey.

These ridges present a hazard to navigation since navigation of deep draft vessels is in close proximity of these ridges. It is recommended that a basic hydrographic survey (Field Examination) be conducted of The Race from Race Rock to Valiant Rock.

It is recommended that the reconnaissance soundings and the estimated least depth of 25 feet at contact #4 plotted on the sounding smooth sheet be charted as "reported" only until a basic survey can be conducted and then removed from the chart since they are unqualified soundings that indicate uncharted shoaling. Contact #4 has only an estimated least depth which is intentionally estimated that the conduct the conduct that indicate uncharted shoaling. least depth which is intentionally estimated at a shoaler depth than probable for this contact. Contacts #1 and #26 compare well with prior hydrography and no additional investigation is recommended.

The present survey is adequate only to supplement prior data. It was not the intent of the present survey to supersede the above prior hydrographic surveys.

b. Wire Drag

H-4008 WD (1917-18) 1:20,000 H-4008a WD (1917-18) 1:20,000

The above prior wire drag surveys cover approximately 95% of the present survey with the areas not covered being in the immediate vicinity of Race Rock and to the east of Race Rock. No conflicts exist between present and prior effective depths. No conflicts exist between prior effective depths and present survey least computed depths (reported depths) by side-scan sonar contacts. The reconnaissance soundings smooth plotted and the estimated least depth (reported depth) on contact #4 are not common to either of these prior surveys.

7. COMPARISON WITH CHART 13212, 29th Edition, January 1, 1983

Hydrography

The charted hydrography originates with the previously discussed prior surveys except possibly the two soundings also discussed. previously discussed prior surveys require no further consideration. The hydrographer makes adequate chart comparisons in the Descriptive Report with the exception of the area in the vicinity of Race Rock. Comments and charting recommendations concerning the area in the vicinity of Race Rock are adequately addressed in section 6. of this report. The hydrographer additionally discussed in section L. of the Descriptive Report work accomplished on a charted obstruction in Latitude 41°16'26"N, Longitude 72°02'39"W. No field data or plots were included

in the survey records and this obstruction is outside the limits and scope of this survey.

b. Aids to Navigation

Only two aids to navigation, Race Rock Light and Valiant Rock Lighted Bell Buoy "1A", are common to the surveyed area. Bartlett Reef Lighted Bell Buoy "4", and New London Harbor Dumping Ground Lighted Buoy "NL" were located by the present survey but are outside the limits of the present survey. It is recommended that these three floating aids to navigation be charted in accordance with the most recent information. Only Race Rock Light is smooth plotted.

8. COMPLIANCE WITH INSTRUCTIONS

This survey adequately complies with the Project Instructions except as noted in the Descriptive Report and this report.

9. ADDITIONAL FIELD WORK

This is a good side-scan sonar and wire drag survey which serves its intended purpose except in the vicinity of Race Rock. Additional work in this area is recommended as noted in section 6. of this report.

10. MISCELLANEOUS

- a. The wire drag data smooth plotted and attached to this report was smooth plotted at the 1:40,000 scale to facilitate the inclusion of the smooth plots in this report on 8½" by 11" mylar sheets. The reconnaissance sounding smooth sheet was smooth plotted at the 1:20,000 scale. This is consistent with section 7.10. of the Project Instructions dated April 12, 1984.
 - b. No splits exist in the area cleared by wire drag.

Marrice B. Hickson, III

Cartographer

Evaluation and Analysis

INSPECTION REPORT FE-262 WD

The completed survey has been inspected with regards to survey coverage, investigation of hangs and clearance depths, cartographic symbolization, and the verification or disproval of charted data. The side scan sonar data have been inspected to gain insight into its overall completeness regarding survey coverage, presentation of survey results, and the verification or disproval of charted data.

The survey, except as noted in the Evaluation Report, is considered completed and adequate to meet National Ocean Service standards. The survey records comply with NOS requirements except as noted in the Evaluation Report. Processing is considered complete.

Inspected

R. D. Sanocki

Chief, Hydrographic Surveys

Processing Section


Hydrographic Surveys Branch


David B. MacFarland, Jr., LCDR, NOAA Chief, Hydrographic Surveys Branch


Approved June 28, 1985


Wesley V Hull, RADM, NOAA


Director, Atlantic Marine Center











DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

National Ocean Survey Rockville, Maryland Hydrographic Index No. 63 L 1967-1975 ISLAND SOUND AND VICINITY Complete through August 1978 INDEX HYDROGRAPHIC SURVEYS LONG Diagram No. 1211-3 -> 7 0 On Scales of 1:10000 6.34 inches=1 statute 1:20000 3.17 inches=1 statute

MARINE CHART BRANCH

RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. FE-262WD

INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

- 1. Letter all information.
- 2. In "Remarks" column cross out words that do not apply.
- 3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

	r		made under "Comparison with Charts" in the Review.
CHART	DATE	CARTOGRAPHER	REMARKS
13205	7-29-85	Barbon Lovete	Full Part Before After Marine Center Approval Signed Via
			Drawing No. 5/ Exam No correction Considered
			Luly applied 1.0 Has comp 0.5-yer
12372	8-23-85	Barbara Loretz	Full Part Before-After Marine Center Approval Signed Via
			Drawing No. # 25A Applied 1.0 HRS Comp. 0.50
100 - 1			
1354	6-11-86	HRadden	Full Part Deficts After Marine Center Approval Signed Via
· · · · · · · · · · · · · · · · · · ·			Drawing No. 56 No corr. App'd. thru 12372
13212	2-7-89	Jeff Taylor	Full Part Before After Marine Center Approval Signed Via
		-	Drawing No. 33
			Full Part Before After Marine Center Approval Signed Via
 		, , , , , , , , , , , , , , , , , , , ,	Drawing No.
13209	5-24-89	Ernet V. Monte	Full Part Defore After Marine Center Approval Signed Via
			Drawing No. 26 App'd Hurough 12372 #25A
13211	3-8-90	EdMartin	Full Part Before After Marine Center Approval Signed Via
			Drawing No. 21
			DUR DE ACTUAL CONTRACTOR DE CO
			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
			Diawing 140.
7			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
		•	
			STANDANDS CK'D 7-22-85 C.lon
			Clay
· · · · · · · · · · · · · · · · · · ·			
			/